

**Town of Eden**  
**Iowa County**  
**Crack Sealing Bid Form**

- Bids are due on Monday May 4th, 2026 at 6:00 pm to the Town Clerk
- Bids will be opened on Monday May 4th, 2026 at 6:00 pm
- **A copy of this form must be filled out as is and included in any bid to be considered.**
- Contractor must supply town with proof of insurance.
- The Town reserves the right to accept or reject any, all, or any portion of bids so that it is most advantageous to the Town.
- Bids are on a line item basis and are considered to be individual bids.
- There is a completion deadline for all projects of August 31, 2026, unless specified otherwise, subject to change per the town board

Company Name - \_\_\_\_\_

Representative - \_\_\_\_\_

Contact # - \_\_\_\_\_

All cracks greater than ¼ inch wide are to be sealed.

Place sealant materials when air and surface temperature at the crack sealing area are 40°F or greater in the shade.

Do not place sealant material if temperatures are predicted to drop below 40°F before the sealant is cured.

Do not place sealant material if weather conditions are rainy or wet. If sealant is placed and rain falls before the sealant has properly cured, remove and replace the wet/contaminated sealant.

Remove failed sealant, dirt, dust and any deleterious material. Dispose of any debris or material removed in preparation of cracks and any over-heated material in a legal and environmentally safe method.

Prepare cracks for sealing on the same day that they are to be sealed.

All new cracks and joints must be routed to a minimum of ¾" x ¾" width versus depth. Cracks shall be blown out with 120 psi compressed air. The road surface shall also be blown off at this time to clear it of any routed debris.

Using the second compressor, the cracks shall be blown out using a heat lance.

All cracks shall be pressure filled by a wand applicator from the bottom up. They shall be slightly overfilled and disc squeegee to create an over-band 1" wide on each side of the routed reservoir. Also include any refilling and/or touching up of any previously filled cracks as needed that are exposed or as directed.

The cracks will then have a single ply toilet paper applied to prevent any material from tacking.

All work to be completed to State of Wisconsin Standards unless specified differently above

Any change request must be submitted in writing

All materials and labor to be provided by the contractor without exception

Any questions can be directed to the Town Patrolman

Traffic control coordinated with the Town

See map for location of road work

# Project List

Work ID	Road Name	Width	Length	Bid Price
Willow Springs Crack 1	Willow Springs Rd State Road 80 past shop	20 Feet	739 Feet	



X \_\_\_\_\_  
Contractor

X \_\_\_\_\_  
Town of Eden

Notes

- 1) Project to be completed by 8/31/2026 subject to change per town board
- 2) Traffic Control shall be incidental to all work performed.

# Project List

Work ID	Road Name	Width	Length	Bid Price
Willow Springs Crack 2	Willow Springs Between Tower and Edgington	20 Feet	704 Feet	



X \_\_\_\_\_  
Contractor

X \_\_\_\_\_  
Town of Eden

Notes

- 1) Project to be completed by 8/31/2026 subject to change per town board
- 2) Traffic Control shall be incidental to all work performed.