

**Town of Eden**  
**Iowa County**  
**Double Chip Sealing Bid Form**

- Bids are due on Monday May 4th, 2026 at 6:00 pm to the Town Clerk
- Bids will be opened on Monday May 4th, 2026 at 6:00 pm
- **A copy of this form must be filled out as is and included in any bid to be considered.**
- Contractor must supply town with proof of insurance.
- The Town reserves the right to accept or reject any, all, or any portion of bids so that it is most advantageous to the Town.
- Bids are on a line item basis and are considered to be individual bids.
- There is a completion deadline for all projects of August 31, 2026, unless specified otherwise, subject to change per the town board

Company Name - \_\_\_\_\_

Representative - \_\_\_\_\_

Contact # - \_\_\_\_\_

Prepare gravel base with proper crowning of road surface.

Application of at least 340 degrees F PG 58-28 asphalt, 5% cutback, by a full-width of (24') unless specified otherwise, spray distributor.

Apply sealcoat cover aggregate, spread uniformly over surface with a full-width self propelled chip spreader.

Roll cover aggregate with pneumatic-tired roller.

Process to be repeated for second layer in accordance with best practice.

Top layer of aggregate to be 3/8" pea stone unless specified otherwise.

All work to be completed to State of Wisconsin Standards unless specified differently above

Any change request must be submitted in writing

All materials and labor to be provided by the contractor without exception

Any questions can be directed to the Town Patrolman

Traffic control coordinated with the Town

See map for location of road work

See addendum for Wolonec Road Bid

# Project List

Work ID	Road Name	Width	Length	Bid Price
Badger Hollow 1	Badger Hollow Purple	16'	1872 Feet	
Badger 1 Grnte	Same as above but with granite	16 Feet	1872 Feet	



X \_\_\_\_\_  
Contractor

X \_\_\_\_\_  
Town of Eden

Notes

- 1) Project to be completed by 8/31/2026 subject to change per town board
- 2) Traffic Control shall be incidental to all work performed.

# Project List

Work ID	Road Name	Width	Length	Bid Price
Badger Hollow 2	Badger Hollow Blue	12 Feet	3590 Feet	
Badger 2 Granite	Same as above but with granite	12 Feet	3590 Feet	



X \_\_\_\_\_  
Contractor

X \_\_\_\_\_  
Town of Eden

Notes

- 1) Project to be completed by 8/31/2026 subject to change per town board
- 2) Traffic Control shall be incidental to all work performed.

# Project List

Work ID	Road Name	Width	Length	Bid Price
Badger Hollow 3	Badger Hollow Yellow	16 Feet	415 Feet	
Badger 3 Granite	Same as above but with granite	16 Feet	415 Feet	



X \_\_\_\_\_  
Contractor

X \_\_\_\_\_  
Town of Eden

Notes

- 1) Project to be completed by 8/31/2026 subject to change per town board
- 2) Traffic Control shall be incidental to all work performed.

# Project List

Work ID	Road Name	Width	Length	Bid Price
Willow Seal	Willow Springs, St Anthony's Corner	20 Feet	1320 Feet	
Willow Granite	Same as above but with granite	20 Feet	1320 Feet	



X \_\_\_\_\_  
Contractor

X \_\_\_\_\_  
Town of Eden

Notes

- 1) Project to be completed by 8/31/2026 subject to change per town board
- 2) Traffic Control shall be incidental to all work performed.

# Wolonec Road Addendum

## Advertisement for Bids:

The Town of Eden is accepting sealed bids for various sealcoat surfacing projects and for an LRIP Pavement Replacement project in the Township. The township will utilize Local Road Improvement Program (LRIP) funds from the 2026-27 Wisconsin biennial budget to reshape the existing base coarse and provide a new asphalt double chipseal layer along Wolonec Road in the township. The Town reserves the right to award the project(s) as listed below to the lowest responsible bidder as determined by the Township. The Town reserves the right to award each of the five projects listed below based on their individual line item project bid prices provided individually or as a combined base bid amount. If there is a deduct or credit proposed by a Contractor should they receive all of the projects in one package versus as proposed by project bid; the Contractor shall separate the quoted credit, so as to individually prorate out the revised cost per project as submitted in the bid form.

The sealed bid quote for Project #5 on Wolonec Road may be awarded separately from other work and shall include all labor, equipment, materials, supplies, and other incidental items as necessary to complete the work. The Contractor shall grade and reshape Wolonec Road from Tower Road to its' terminus. The work shall include adding crushed aggregate base coarse as deemed necessary to re-establish a 2% normal crown at an 18-foot (eighteen minimum roadway surface width) centered on the roadway centerline for drainage purposes. Placement of a sealcoat oil and base surface in two repetitive lifts will be required. The first coat of oil shall be placed as determined by the aggregate analysis recommendation or at a rate of  $\pm 0.42$  Gals/SYd; as adjusted in the field for adequate coverage of the aggregate material. The second lift shall be done at 0.36Gals/Sq Yd or as adjusted for adequate coverage of the aggregate materials.

# Project List

This Project is an LRIP Project

Work ID	Road Name	Width	Length	Bid Price
Wolonec Seal	Wolonec Rd, Tower to End	16 Feet	3907 Feet	
	Same as above but with granite	16 Feet	3907 Feet	



X \_\_\_\_\_  
Contractor

X \_\_\_\_\_  
Town of Eden

Notes

- 1) Project to be completed by 8/31/2026 subject to change per town board
- 2) Traffic Control shall be incidental to all work performed.